

Flow chart „total process“ of upcoming service measure

Trailer builder or BPW, partly in charge of trailer builders, informs the end user officially .

Immediate action until the workshop date for service measure:
 a) Check the brake disc daily for corrosion (Are there any significant signs of corrosion visible on friction surfaces of each brake discs?)
 b) Are there any noticeable temperature differences of each wheel hub after finishing the trip?
 c) Compliance of BPW maintenance instructions in half year periods, check the brake disc and caliper guiding (clearance)

Anomalies?

Yes

Visit the workshop immediately to check the brakes

No

Axle production 2019 und 2020

Axle production 2021

Brake roll test promptly

Brakes OK?

No

Replace the affected brake caliper

Yes

Trailer can be operated further

End user makes an appointment with the workshop max. 6 months after the brake roll test to let carry out the functional check.

Date for functional check possible?

No

Repeat check „brake roll test“ after max. 6 months

Yes

Carry out the service measure BPW ECO Disc Trailer disc brakes (see subprocess „functional check“), if necessary change the caliper

Service measure is completed for this trailer.

